

# Max-Planck-Institut für Plasmaphysik

## Thermal loading test of a Wendelstein 7-X pumping gap panel


J. Boscary\*<sup>1</sup>, F. Schauer<sup>1</sup>, B.-E. Ghidersa<sup>2</sup>, R. Krüßmann<sup>2</sup>, M. Lux<sup>2</sup>, M. Czerwinski<sup>3</sup>, Z. Wang<sup>1</sup>, C. Li<sup>1</sup>, B. Mendelevitch<sup>1</sup>, G. Ehrke<sup>3</sup>, and the W7-X Team<sup>4</sup>

<sup>1</sup>Max-Planck-Institut für Plasmaphysik, 85748 Garching, Germany  
<sup>2</sup>Karlsruher Institut für Technologie (KIT), Karlsruhe, Germany  
<sup>3</sup>Max-Planck-Institut für Plasmaphysik (IPP), Greifswald, Germany  
<sup>4</sup>T. Klinger et al., Nucl. Fusion 59 (2019) 112004 doi: 10.1088/1741-4326/ab03a7



### Abstract/Motivation

- For the upcoming long pulse operation phase "OP2" of Wendelstein 7-X (W7-X), new water cooled non planar stainless steel panels have been manufactured to protect the wall of the plasma vessel behind the divertor pumping gap
- A panel is made of a machined ground plate with channels which are covered by likewise machined sheets. The latter are electron-beam welded to the ground plates
- There are 60 panels of 7 different types which are designed to remove a stationary heat flux up to 100 kW/m<sup>2</sup>. The specified water cooling conditions are: 2.5 MPa inlet pressure, 30°C inlet temperature, and 0.27 l/s flow rate.
- A panel prototype has been manufactured and thermal loaded in the facility SIRHEX at the KIT to about 100 kW/m<sup>2</sup> to validate the design and manufacturing process.
- The results of the loading experiment and of the comparison to simulation performed with the software ANSYS® CFX are presented.


### CAD Model of the pumping gap panels




### Full-scale Prototype



### Thermal loading test in SIRHEX



### Comparison with simulation



Comparison between measurements and calculation of thermocouple temperatures

	Thermocouple [°C]	1	2	3	4	5	6	7	8	9	10
Case 1	Measurement	61	110	85	134	142	89	96	104	98	250
	Calculation	70	120	95	140	130	90	90	110	95	250
Case 2	Measurement	75	126	100	152	159	103	108	115	108	255
	Calculation	85	130	110	150	155	100	110	125	110	260

### Conclusions

- A full-scale prototype has been successfully tested in the SIRHEX facility at KIT
- A good agreement between ANSYS® CFD simulations and measurements has been found
- The water-cooled panel is able to withstand 100 kW/m<sup>2</sup> under stationary conditions
- The design of the cooling channel allows a quite homogeneous surface temperature distribution and sufficient cooling at the edges
- Results of the thermal loading test validate the design and manufacturing process of the pumping gap panels for the next operation phase (OP2) of W7-X